The 31st December 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 31st January 1889, for constructing a new anicut across the Veda River to feed the Chikkapatnagere Tank, Registered No. 969 of Kadur-Taluk, with other dependent works. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chimagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Abstract.

Items of Work.	Per.	Quantity.	Rate.
Earthwork excavation deep cutting	C. Yd.	26,400	
Do do including watering and tamping ..	do	14,029	
Do ordinary cutting	do	27,998	
Benching rock	do	54	
Mile stones	No.	6	
Furlong stones	do	42	
Index stones	do	47	
Grade stones	do	47	
Madaboys	Each.	..	
Excavating foundation for aqueducts & relieving weirs ..	L. S.	..	
Rough stone in surki mortar	C. Ft.	9,369	
Chunam surki plastering	Sqr.	77·25	
Burnt stone slabs dressed, set in mortar	S. Ft.	3,850	
Teak wood work including tarring ..	C. Ft.	48	
Dry rough stone work	C. Yd.	430	
Burnt stone in surki mortar	C. Ft.	25,831	
Surki chunam pointing	Sqr.	82·50	
Concrete work	C. Ft.	575	
Archwork burnt stone in surki mortar	do	1,369	
Brick cornice work	R. Ft.	308	
Cornice work cut stone	do	46	
Constructing two broad cattle bridges ..	Each.	..	

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing a new anicut across the Veda River to feed the Chikkapatnagere Tank, Registered No. 969 of Kadur Taluk, with other dependent works;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 25th January 1889, for restoring the Birur Devankere, Registered No. 791, Kadur Taluk, including kodis and sluices. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Abstract.

Items of Work.	Per.	Quantity.	Rate.
Earthwork cutting and filling bund	C. Yd.	469	
Do including watering and tamping ..	..	18,183	
Do excavation	...	367	
New rough stone work	..	2,465	
Old do	..	2,376	
Grade stones	No.	68	
B. M. stones	..	2	
Gauge stones	R. Ft.	20	
Brick in surki mortar	C. Ft.	8,395	
Surki chunam plastering	Sqr.	50·14	
Burnt stone slabs	S. ft.	29·85	
Concrete work	C. ft.	1,185	

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring the Birur Devankere, Registered No. 791, Kadur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. SITARAM RAO,
Executive Engineer.

SHIMOGA DIVISION.

ADVERTISEMENT.

The 15th December 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th January 1889 for restoring Danavadi Dymanakere in Shimoga Taluk, which is expected to be sanctioned shortly. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A. M. and 5 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed or should specify ( ) per cent less on estimated rates.